



सरदार वल्लभभाई पटेल राष्ट्रीय पुलिस अकादमी
SARDAR VALLABHBHAI PATEL NATIONAL POLICE ACADEMY
(भारत सरकार : गृह मंत्रालय)

(Government of India : Ministry of Home Affairs)

हैदराबाद - 500 052, Hyderabad - 500 052.

No.11011/1/2015-16/HS-Bldgs

Dated, the 15 Feb 2016

NOTICE INVITING TENDER

To

As per list enclosed

Sub: Tender Enquiry Notice for providing and laying of bituminous road (Front of kill house area) inside Site-'B' of SVP NPA Hyderabad- Request for furnishing quotation - Reg.

Sardar Vallabhbhai Patel National Police Academy, Hyderabad, the premier Police Training Institution of our country, invited quotations for providing and laying of bituminous road (Front of kill house area) inside Site-'B' of SVP NPA Hyderabad as per details given below :-

1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed. Hard rock (blasting prohibited)
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) cum 892.70
3	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.
4	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion On W.B.M / W.M.M. @ 0.4kg/sqm On bituminous surface @ 0.25kg/sqm
5	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem

	rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.
6	Providing and laying semi- dense Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 25 mm compacted thickness with bitumen of grade VG- 30 @5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity.
7	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.

2). Terms and Conditions

- a) The bidders should have at least five years of experience in the field and must enclose copy of their firm's registration certificate along with the quotation.
- b) Site Visit :- Interested vendors may visit the site before submitting the quotation after taking prior permission from the Assistant Commandant (Works) of SVP NPA Hyd..
- c) Earnest Money Deposit :- EMD of Rs.10000/- (Rupees ten thousand only) should be enclosed in the form of demand draft drawn in any commercial bank in favour of 'The Director, S.V.P. National Police Academy, Hyderabad'. Offers received without the prescribed EMD, will be rejected summarily. No interest will be paid on Earnest Money Deposit. EMD of unsuccessful tenderers will be returned in due course of time
- d) Terms of payment - No advance payment or payment against proforma invoice will be made. Payment will be made only after completion of work
- e) The work should be completed within 10 days from the date of receipt of work order from the Academy
- f) The bid should be valid for 180 days from the date of opening of bid.

- g) The scope of work as defined above shall be strictly adhered to.
- h) In case of deviations, the same shall be explicitly indicated in a separate statement
- i) The total cost of work shall be indicated including all taxes and the rates shall remain firm and fixed and shall not be subjected to any variation at any stage of execution
- j) The period of completion of the work shall be indicated in the offer.
- k) SVP NPA shall not be responsible for postal delay or any other delay in respect of submission of the bid / delay in receipt of the bid and such bid will be summarily rejected.
- l) The work once entrusted, shall be completed in the time frame as stipulated in the work order and in case of delay a penalty of 1% of the contract value is liable to be deducted from the final payment, for every week's delay.
- m) In case of inordinate delay, the Academy reserves every right to cancel the work order, without any liability including forfeiting the EMD/Security deposit submitted, as the case may be.
- n) The bidder will be blacklisted by the Academy in case of (column-n) above being invoked.
- o) Water and electricity charges arising during the period of execution, shall be to the Contractors account
- p) Warranty - The work executed shall carry a minimum warranty period of 01 year from the date of completion and handing over of the work.
- q) Performance security :- The successful bidder shall have to deposit a performance security of 5% of the contract value of the supply / work order rounded up to next hundred in the form of account payee demand draft / bank guarantee from a nationalized / scheduled commercial bank in favour of the Director, SVP NPA Hyderabad payable at SBH Shivrampally, Hyderabad within 15 days of the placement of supply order for due performance as per the provisions contained in GFR - 158. Failure on the part of the firm to deposit the performance security within stipulated time the purchaser reserves the right to cancel the Supply Order. Performance Security submitted by the bidder will remain valid for a period of sixty days beyond the date of completion of all contractual obligations of the supplier including warranty obligations. No interest will be payable for "Performance Security

3). Parties interested in carrying out the above work and on acceptance of the above terms and conditions, may submit their quotation along with EMD in a sealed cover addressed to the undersigned and duly superscribed as "providing and paying of bituminous road (Front of kill house area) inside Site-'B' of SVP NPA Hyderabad"- Not to be opened before 25 Feb 2016 (1700 hrs).

4) The last date for receipt of quotations is 25 Feb 2016 at 1700 Hrs.

Yours faithfully,



(K. Shankar)
Administrative Officer (Admn.)
SVP National Police Academy
Shivrampally,
Hyderabad-500 052

Copy to:

1. AC (Works) for information and necessary action.
2. Main office Notice Board.
3. Computer Section for hosting the notice in Academy website.

