



सरदार वल्लभभाई पटेल राष्ट्रीय पुलिस अकादमी  
SARDAR VALLABHBHAI PATEL NATIONAL POLICE ACADEMY  
(भारत सरकार : गृह मंत्रालय)

(Government of India : Ministry of Home Affairs)

हैदराबाद — 500 052Hyderabad – 500 052.

No.11011/1/2017-18/HS-Bldgs

Dated, the 8 August 2017

**NOTICE INVITING TENDER**

To

As per list enclosed

Sub: **Tender Enquiry Notice for Construction of Choked Drain at Stadium in Site-B of SVP NPA Hyderabad-Regarding.**

Sardar Vallabhbhai Patel National Police Academy, Hyderabad, the premier Police Training Institution of our country, invites quotations for Construction of Choked Drain at Stadium in Site-B of the Academy as per details given below :-

S.No.	Description of Item	UNIT	QTY
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed :		
1.1	All kinds of soil	sqm	24.96
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.		
2.1	All kinds of soil.	cum	13.16
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level:		
3.1	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	cum	2.93
4	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in:		
4.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	6.73
5	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. complete.		
5.1	Hot finished welded type tubes.	Kg	800.00

6	15mm cement plaster on the rough side of single or half brick wall of mix:		
6.1	1:4 (1 cement : 4 fine sand)	sqm	70.20
7	Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineer in-Charge.		
7.1	60mm thick Cement concrete paver block of M-35 grade with approved colour, design & pattern.	sqm	24.96

## 2) Terms and Conditions

- a) The bidders should have at least two years of experience in the field and must enclose copy of certificate of their firm's registration with CPWD or any other Govt agencies along with the quotation.
- b) Site Visit :- Interested vendors may visit the site before submitting the quotation after taking prior permission from the Assistant Commandant (Works) of SVP NPA Hyd.
- c) Earnest Money Deposit :- EMD of Rs. 4000/- (Rupees Four thousand only ) should be enclosed in the form of demand draft drawn in any commercial bank in favour of 'The Director, S.V.P. National Police Academy, Hyderabad'. Offers received without the prescribed EMD, will be rejected summarily. No interest will be paid on Earnest Money Deposit. EMD of unsuccessful tenderers will be returned in due course of time
- d) Terms of payment – No advance payment or payment against proforma invoice will be made. Payment will be made only after completion of work.
- e) The work should be completed within 30 days from the date of receipt of work order from the Academy
- f) The bid should be valid for 180 days from the date of opening of bid.
- g) The entire scope of work as defined above shall be treated as a single work and no offer in piece meal shall be accepted
- h) In case of deviations, the same shall be explicitly indicated in a separate statement
- i) The total cost of work shall be indicated including all taxes and the rates shall remain firm and fixed and shall not be subjected to any variation at any stage of execution
- j) SVP NPA shall not be responsible for postal delay or any other delay in respect of submission of the bid / delay in receipt of the bid and such bid will be summarily rejected.

- k) The work once entrusted, shall be completed in the time frame as stipulated in the work order and in case of delay a penalty of 1% of the contract value is liable to be deducted from the final payment, for every week's delay.
- l) In case of inordinate delay, the Academy reserves every right to cancel the work order, without any liability including forfeiting the EMD/Security deposit submitted, as the case may be.
- m) The bidder will be blacklisted by the Academy in case of (column-l) above being invoked.
- n) Water and electricity charges arising during the period of execution, shall be to the Contractors account
- 3) Parties interested in carrying out the above work and on acceptance of the above terms and conditions, may submit their quotation along with EMD in a sealed cover addressed to the undersigned and duly super scribed as "Construction of Choked Drain at Stadium in Site-B of SVP NPA Hyderabad".- Not to be opened before 14<sup>th</sup> Aug2017 (1700 hrs)
- 4) The last date for receipt of quotations is 14<sup>th</sup> Aug 2017 at 1700 Hrs.

Yours faithfully,



Administrative Officer (Admn.)  
SVP National Police Academy  
Hyderabad-500 052

Copy to:

1. AC (Works) for information and necessary action.
2. Main office Notice Board.
3. Computer Section for hosting the notice in Academy website.



