



सरदार वल्लभभाई पटेल राष्ट्रीय पुलिस अकादमी
SARDAR VALLABHBHAI PATEL NATIONAL POLICE ACADEMY
(भारत सरकार : गृह मंत्रालय)

(Government of India : Ministry of Home Affairs)

हैदराबाद - 500 052, Hyderabad - 500 052.

No.11011/1/2017-18/HS-Bldgs

Dated, the 22 June 2017

NOTICE INVITING TENDER

To

As per list enclosed

Sub: **Tender Enquiry Notice for construction of two rooms (size 1.80x2.1 mtr) for keeping moving target motors at Firing range at Site-B of SVP NPA Hyderabad-Regarding.**

Sardar Vallabhbhai Patel National Police Academy, Hyderabad, the premier Police Training Institution of our country, invites quotations for construction of two rooms (size 1.80x2.1 mtr) for keeping moving target motors at Firing range at Site-B of the Academy as per details given below :-

S no	Description of Item	unit	Qty
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed :		
1.1	All kinds of soil	Sqm	13.20
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.		
2.1	All kinds of soil	Cum	6.34
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed.		
3.1	Ordinary rock	Cum	6.34
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :		
4.1	1:5:10 (1 Cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	Cum	1.91

5	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like.		
5.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	10.37
6	Brick work with common burnt clay F.P.S. (non modular) bricks		
6.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	11.54
7	12 mm cement plaster of mix :		
7.1	1:4 (1 cement: 4 coarse sand)	Sqm	50.16
8	12 mm cement plaster finished with a floating coat of neat cement of mix :		
8.1	1:3 (1 cement: 3 fine sand)	Sqm	7.56
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :		
9.1	1:1½:3 (1 cement:1½ coarse sand:3 graded stone aggregate 20 mm nominal size)	sqm	4.34
10	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.		
10.1	Using M.S. angels 40x40x6 mm for diagonal braces	sqm	6.66
11	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	kg	179.04
12	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 micron epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	10.92


13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work sqm 74.40		
13.1	Two or more coats on new work	sqm	17.95
14	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :		
14.1	Two or more coats on new work	sqm	50.16
15	Providing and fixing of electrical connections of rooms including wiring moulder switches and board and tube lights etc complete of iteam.	Job	2.00

2) **Terms and Conditions**

- a) The bidders should have at least two years of experience in the field and must enclose copy of certificate of their firm's registration with CPWD or any other Govt agencies along with the quotation.
- b) **Site Visit** :- Interested vendors may visit the site before submitting the quotation after taking prior permission from the Assistant Commandant (Works) of SVP NPA Hyd.
- c) **Earnest Money Deposit** :- EMD of Rs. 4,800/- (Rupees four thousand eight hundred only) should be enclosed in the form of demand draft drawn in any commercial bank in favour of 'The Director, S.V.P. National Police Academy, Hyderabad'. Offers received without the prescribed EMD, will be rejected summarily. No interest will be paid on Earnest Money Deposit. EMD of unsuccessful tenderers will be returned in due course of time
- d) **Terms of payment** – No advance payment or payment against proforma invoice will be made. Payment will be made only after completion of work.
- e) The work should be completed within 20 days from the date of receipt of work order from the Academy
- f) The bid should be valid for 180 days from the date of opening of bid.
- g) The entire scope of work as defined above shall be treated as a single work and no offer in piece meal shall be accepted
- h) In case of deviations, the same shall be explicitly indicated in a separate statement
- i) The total cost of work shall be indicated including all taxes and the rates shall remain firm and fixed and shall not be subjected to any variation at any stage of execution
- j) SVP NPA shall not be responsible for postal delay or any other delay in respect of submission of the bid / delay in receipt of the bid and such bid will be summarily rejected.
- k) The work once entrusted, shall be completed in the time frame as stipulated in the work order and in case of delay a penalty of 1% of the contract value is liable to be deducted from the final payment; for every week's delay.
- l) In case of inordinate delay, the Academy reserves every right to cancel the work order, without any liability including forfeiting the EMD/Security deposit submitted, as the case may be.
- m) The bidder will be blacklisted by the Academy in case of (column-l) above

- being invoked.
- n) Water and electricity charges arising during the period of execution, shall be to the Contractors account
- 3) Parties interested in carrying out the above work and on acceptance of the above terms and conditions, may submit their quotation along with EMD in a sealed cover addressed to the undersigned and duly superscribed as **"construction of two rooms (size 1.80x2.1 mtr) for keeping moving target motors at Firing range at Site-B of SVP NPA Hyderabad". - Not to be opened before 13 July 2017 (1700 hrs)**
- 4) The last date for receipt of quotations is **13 July 2017 at 1700 Hrs.**

Yours faithfully,



Administrative Officer (Admn.)
SVP National Police Academy
Hyderabad-500 052

Copy to:

1. AC (Works) for information and necessary action.
3. Computer Section for hosting the notice in Academy website.

