



सरदार वल्लभभाई पटेल राष्ट्रीय पुलिस अकादमी
SARDAR VALLABHBHAI PATEL NATIONAL POLICE ACADEMY
(भारत सरकार : गृह मंत्रालय)

(Government of India : Ministry of Home Affairs)

हैदराबाद - 500 052, Hyderabad - 500 052.

No.11011/1/2017-18/HS-Bldgs

Dated, the ___ May 2017

NOTICE INVITING TENDER

To

As per list enclosed

Sub: **Tender Enquiry Notice for providing and fixing of false ceiling, profile sheet and internal painting works at Mini Library, Water Plant, Library store room at Site-A of SVP NPA Hyderabad-Regarding.**

Sardar Vallabhbbhai Patel National Police Academy, Hyderabad, the premier Police Training Institution of our country, invites quotations for providing and fixing of false ceiling, profile sheet and internal painting works at Mini Library, Water Plant, Library store room at Site-A of the Academy as per details given below :-

Sl.No.	Description of Item	unit	Qty
1	Providing and fixing pre coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50mm +/- 5% total coated thickness (TCT) Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat' 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-Charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal / vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	220.00

2	Providing and fixing precoated galvanized steel sheet roofing accessories 0.50mm +/- 5% total coated thickness (TCT) Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling / self tapping screws or with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers complete:		
2.1	Ridges plain (500 - 600mm).	meter	29.00
3	Providing and Fixing 15 mm thick densified regular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture spin tone/cosmos / Hexa or equivalent of size 595 x 595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanizing @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38mm made from 0.33 mm thick (minimum) sheet, spaced 1200mm centre to centre, and cross "T" of size 24x28mm made out of 0.33mm (Minimum) sheet, 1200mm long spaced between main 'T' at 600mm centre to centre to form a grid of 1200x600mm and secondary cross 'T' of length 600mm and size 24 x28mm made of 0.33mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600mm panel to form grid of size 600x600mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450mm centre to centre with 25mm long dry wall screws @ 230mm interval and laying 15mm thick densified edges calcium silicate ceiling tiles of approved texture (Spin tone / Cosmos/hexa) in the grid including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., where ever required, Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6mm fixed to ceiling with 12.5 mm dia and 50mm long dash fasteners, 4mm G.I. adjustable rods with galvanized steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200mm centre to centre along main 'T' , bottom exposed with 24mm of T-sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by engineer-in-charge.		
3.1	Note :- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/opening (cut outs) having area less than 0.30 sqm. The calcium silicate ceiling tile shall have NRC. value of 0.50(Minimum), light reflection > 85%, non - combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity<0.043 w/m 0 KC.	sqm	27.00

4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:		
4.1	Two or more coats on new work	sqm	275.00
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:		
5.1	Two or more coats on new work	sqm	9.00

2) **Terms and Conditions**

- a) The bidders should have at least two years of experience in the field and must enclose copy of certificate of their firm's registration with CPWD or any other Govt agencies along with the quotation.
- b) **Site Visit** :- Interested vendors may visit the site before submitting the quotation after taking prior permission from the Assistant Commandant (Works) of SVP NPA Hyd.
- c) **Earnest Money Deposit** :- EMD of Rs. 5000/- (Rupees five thousand only) should be enclosed in the form of demand draft drawn in any commercial bank in favour of 'The Director, S.V.P. National Police Academy, Hyderabad'. Offers received without the prescribed EMD, will be rejected summarily. No interest will be paid on Earnest Money Deposit. EMD of unsuccessful tenderers will be returned in due course of time
- d) **Terms of payment** – No advance payment or payment against proforma invoice will be made. Payment will be made only after completion of work.
- e) The work should be completed within 20 days from the date of receipt of work order from the Academy
- f) The bid should be valid for 180 days from the date of opening of bid.
- g) The entire scope of work as defined above shall be treated as a single work and no offer in piece meal shall be accepted
- h) In case of deviations, the same shall be explicitly indicated in a separate statement
- i) The total cost of work shall be indicated including all taxes and the rates shall remain firm and fixed and shall not be subjected to any variation at any stage of execution
- j) SVP NPA shall not be responsible for postal delay or any other delay in respect of submission of the bid / delay in receipt of the bid and such bid will be summarily rejected.
- k) The work once entrusted, shall be completed in the time frame as

stipulated in the work order and in case of delay a penalty of 1% of the contract value is liable to be deducted from the final payment, for every week's delay.

- l) In case of inordinate delay, the Academy reserves every right to cancel the work order, without any liability including forfeiting the EMD/Security deposit submitted, as the case may be.
 - m) The bidder will be blacklisted by the Academy in case of (column-l) above being invoked.
 - n) Water and electricity charges arising during the period of execution, shall be to the Contractors account
- 3) Parties interested in carrying out the above work and on acceptance of the above terms and conditions, may submit their quotation along with EMD in a sealed cover addressed to the undersigned and duly superscribed as **"Providing and fixing of false ceiling, profile sheet and internal painting works at Mini Library, Water Plant, Library store room at Site-A of SVP NPA Hyderabad".- Not to be opened before 19 May 2017 (1700 hrs)**
- 4) The last date for receipt of quotations is **19 May 2017 at 1700 Hrs.**

Yours faithfully,



Administrative Officer (Admn.)
SVP National Police Academy
Hyderabad-500 052

Copy to:

1. AC (Works) for information and necessary action.
2. Main office Notice Board.
3. Computer Section for hosting the notice in Academy website.

